

House of Building Ltd, 5 Church Street, Reigate RH2 0AA Tel: 01737 219641 E-mail: info@houseofbuilding.co.uk

Name		Name	Cobham
House Number or Name	<u>Quotation</u>	Spec	Gold
Street		Length	5
Town		Depth	5
Postcode	Me	eterage Area	25
		Height	2485
Tel:	Internal of	ceiling height	2100
Email:	Perimeter Line	ar Meterage	20
	External Wall Line	ear Meterage	18.6
Date	Internal Wall Line	ear Meterage	14.6
	Interr	nal Meterage	19.2
Cobham	Decking & So	ffit Meterage	4

Prelims & General

4 weeks Porta loo hire 2 x 6yrd Skips (if additional skips required extra unit price added) Delivery and loading of all equipment

Demolition

N/A

Ground Works

Excavation of oversite 300mm
Grabs Lorry removal of spoils
250mm x 47mm timber fixed and set in excavated area
150mm compacted hardcore to oversite
6mm A142 mesh reinforcement bars laid within oversite © 3.6 m x 2m
150mm STI mix concrete laid to oversite and filling 150mm wide perimeter with 300mm in depth
Brick course laid

Wall Construction

100mm x 47mm Timber stud walls @ 400mm Centres @ 3m Lengths Steel beam 102 x 102 above Door opening set 2110mm from top of brick Metal wall straps 11mm Osb boards fixed to external side Install Breathable mebrane to OSB Attach timber battens to Osb walls at 600mm Horizontal to allow fixing to Vertical Cladding Supply Composite Vertical cladding Supply Composite Vertical reveel trims Supply Composite Vertical cladding Corners Install Cladding 80mm cellotex fixed inside walls Clear DPM 500 gauge Vapour Barrier to ceiling Plasterboard all new stud walls Plastering to all walls Supply and fix 100m mdf Skirting boards Emulsion to walls and two coat painting to skirting board

4.4

Roof & Ceiling Construction

Forming of 150 x 47 flat roof joists
50mm Furring pieces laid to a fall
18mm T&G Osb standard Board fixed to timbers
250mm Textured grey RAL7016 Upvc fascia
250mm Textured grey RAL7016 Upvc Joiner
250mm Textured grey RAL7016 Upvc Joiner
Poly top nails and activater glue
25mm over fascia roof vents
Supply & Install Composite Horizontal Cladding to soffit
Covering of New flat roof using EPDM Roofing system
New gutters and down pipe
Supply and install water butt

80mm Insulation in between ceiling joists. Clear Vapour Barrier to ceiling Plasterboard to ceiling

Plastering to new ceiling Emulsion to ceiling

<u>Floor</u>

1200 gauge DPC Visqueen membrane
80mm cellotex Insulation to floor slab
22mm interlocking boards glued and laid on top of cellotex and pinned down by skirting
Self level latex 3mm to prepare for Karndeen / Amtico
Supply Karndeen / Amtico (style chosen by client)
Lay Karndeen / Amtico straight design (Herrigbone Style Upgrade £15 @ m)

Windows and Doors	Width	Height
Supply and install double glazed Alu K aluminium bi-folding doors	4	2.1
<u>Heating</u>		Incuded Qty
Air conditioning Nano unit		1
Electrics		
Small consumer Unit with Earth Rod Fused isolater in main house 20 m Allowance of Armoured cable run and clipped to existing Internet extension from main house run alongside armoured cable Full Test Certificate 7 W LED Down light White / Chrome Light switch 2 Gang Light switch dimmer 2 Gang Power socket White Power socket White with USB Port TV Point connected only to internet supply DSSO Power Point Up & Down light Brushed Chrome soffitt lights	No Trench included unless requested	1 1 20 1 1 6 1 1 3 1 1 1 2 4

<u>Finishings</u>

Wash cladding & Decking & Spring clean inside Clear site Mastic sealing to all joints on floor around doors etc.

Landscaping

Supply Composite decking Joists
Supply Composite decking secret fixings
Supply Sumo grip sealant
Supply Composite decking 4 m hollow board
Supply Composite decking to face up upstand to side
Supply Composite decking front Corner trim
Installation of Decking

Note: any items required that are not listed above will be charged additionally

I trust that this quotation meets with your approval. However, please do not hesitate to contact me should you have any questions or require any further information.





ontact me

NET

VAT

TOTAL



